

GMP offers four (4) sizes of handline for use in outside plant splicing operations. All sizes are made from manila rope.

5/8 in. Underground Handline

This handline is intended for lowering tools and materials and for setting up cables when doing underground work.

- ▶ Our 5/8 in. x 20 ft. (16 mm x 6 m) handline comes equipped with a 1 in. (25 mm) open hook spliced in one end and a 6 in. (152 mm) eye splice at the other end

P/N 68592 Weight: 3 lbs. (1.5 kg)



1/2 in. Utility Handline

This handline is intended for general construction use.

- ▶ The 1/2 in. x 60 ft. (13 mm x 18 m) handline comes equipped with a crown splice on one end (no hardware) and a 6 in. (152 mm) eye splice on the other end and waxed linen cord served at both ends for approximately 1/2 in. (13 mm)

P/N 68596 Weight: 3 lbs. (1.5 kg)



3/8 in. Utility Handline

Available in lengths of either 50 ft. (15 m) or 100 ft. (30 m), this handline is used to raise service drop wires to pole mounted aerial distribution cable plant.

- ▶ Similar in construction to the 1/2 in. Utility Handline, the 3/8 in. (10 mm) Utility Handlines are provided with a crown splice on one end (no hardware) and a 6 in. (152 mm) eye splice on the other end. Also, both ends are served with approximately 1/2 in. (13 mm) of waxed linen cord.



P/N	Description	Weight
68593	3/8 in. x 50 ft. (10 mm x 15m)	3 lbs. (1.5 kgs)
68595	3/8 in. x 100 ft. (10 mm x 30m)	4 lbs. (2 kgs)